

	Case Name: <b>Gabala Resort Outdoor Pool</b>	Sector	Construction (Commercial Building)
	<b>OR-AS</b> Operations Research - Applications and Solutions <a href="http://www.or-as.be">www.or-as.be</a> <a href="mailto:info@or-as.be">info@or-as.be</a>	<b>Baseline Schedule</b> Schedule with resources Schedule with costs	<b>Risk Analysis</b> Random simulation One of nine std. scenarios User defined distributions
Submitted by	Aleksandra Kostadinova		
Date	December 20, 2012		
File Name	C2012-10 Gabala Resort Outdoor Pool.p2x	<b>Project Control</b> Automatic tracking Tracking based on user input	

## 1. Project description

Project authenticity

The construction of an outdoor pool in the Gabala Resort, situated in the eponymous district of Azerbaijan (Eastern Europe).

The project consists of activity, resource and cost data that were created by the user.

## 2. Project properties

### 2.1. Baseline Schedule

General	
# Activities	18
Planned Duration (PD)	54 days*
Budget At Completion (BAC)	47.413 €
Renewable Resources	9
Consumable Resources	-

\* standard eight-hour working days

Network topology	
Serial/Parallel (SP)	82%
Activity Distribution (AD)	85%
Length of Arcs (LA)	0%
Topological Float (TF)	21%

### 2.2. Risk Analysis

Random simulation by ProTrack was performed using the default symmetric triangular risk distribution profiles.

	Cost sensitivity		
	avg [%]	std dev [%]	skew [-]
CRI-r	17.4	16.8	1.4
CRI-rho	21.2	16.4	1.2
CRI-tau	22.9	22.7	2.2

	Resource sensitivity		
	avg [%]	std dev [%]	skew [-]
CRI-r	34.1	24.6	0.1
CRI-rho	32.8	23.4	0.1
CRI-tau	22.9	12.8	0.1

	Time sensitivity		
	avg [%]	std dev [%]	skew [-]
CI	83.3	37.3	-2.0
SI	1.7	3.8	2.1
SSI	20.4	15.4	0.2
CRI-r	18.2	16.0	0.5
CRI-rho	20.4	13.1	0.7
CRI-tau	19.1	11.7	0.2

## 2.3. Project Control

### 2.3.1. Simulated forecasting accuracy

The accuracy of time and cost forecasting methods has been evaluated based on Monte Carlo simulation runs using the risk profiles described in section “2.2. Risk Analysis”. Based on these risk profiles, the Mean Absolute Percentage Error (MAPE) and Mean Percentage Error (MPE) has been calculated to evaluate the expected accuracy of the time and cost predictions, EAC(t) and EAC, respectively.

Simulated EAC(t) accuracy			Simulated EAC accuracy		
method - PF	MAPE [%]	MPE [%]	method (PF)	MAPE [%]	MPE [%]
PV - 1	1.6	0.2	1	0.8	-0.2
PV - SPI	2.9	0.9	CPI	1.7	-0.2
PV - SCI	4.6	0.9	SPI	2.3	0.4
ED - 1	1.7	0.3	SPI(t)	2.3	0.2
ED - SPI	2.9	0.8	SCI	3.6	0.4
ED - SCI	4.0	0.8	SCI(t)	3.6	0.1
ES - 1	1.2	0.0	0.8 CPI + 0.2 SPI	1.8	0.0
ES - SPI(t)	2.5	0.3	0.8 CPI + 0.2 SPI(t)	1.8	-0.1
ES - SCI(t)	3.7	0.3			

According to the MAPE values<sup>1</sup> the best performance for time forecasting can be expected from the unweighted Earned Schedule method. For cost forecasting the unweighted method should yield the best results.

### 2.3.2. Tracking description

The user has not performed any project control and therefore no tracking periods have been defined. Tracking periods can now be generated automatically by ProTrack or by manually inputting tracking data period by period.

---

<sup>1</sup> The MAPE gives the best indication for the forecast accuracy (the lower the MAPE, the more accurate the method) since all deviations from the targeted real duration (real cost) are cumulated, whereas for the MPE underestimates can be compensated by overestimates and vice versa, possibly leading to an overly positive evaluation of a certain method. However, the MPE can provide useful information about the nature of the deviations, i.e. does the method rather underestimate or overestimate the real duration (real cost)?